

SIGNATURE PAGE

MARBRO, INC.

To the Board of County Commissioners of the County of Monmouth:


**THE UNDERSIGNED HEREBY DECLARES THAT
I (WE) HAVE CAREFULLY EXAMINED THE SPECIFICATIONS.
I (WE) HEREBY CERTIFY PRICES QUOTED ARE IN ACCORDANCE
WITH YOUR REQUIREMENTS.**

Company Name: MARBRO, INC.

(PRINT)

Preparer's Name: FRANK MARUCCI JR
PRESIDENT

(PRINT)

Signature: 

(DATE)

10/19/22

Address: MARBRO, INC.
127 Pine Street
P.O. Box 134
Montclair, NJ 07042

Telephone No.: 973-744-8383

Fax No.: 973-746-5898

E-Mail Address: mar9400@comcast.net

Contact Person: FRANK MARUCCI JR
PRESIDENT

FEIN:
(Federal Employee ID)

SCHEDULE OF QUANTITIES & PRICES

Project Entitled:

**REPLACEMENT OF BRIDGE R-5
ON COUNTY ROUTE 39 (FLORENCE
AVENUE) OVER CHINGARORA CREEK
IN THE BOROUGH OF UNION BEACH,
MONMOUTH COUNTY, NEW JERSEY**

F-53-2022

ITEM No.	EST. QTY.	UNIT	DESCRIPTION	UNIT PRICE	AMOUNT
1	1	LS	Progress Schedule	\$ 2500	\$ 2500
2	4	UNIT	Progress Schedule Update	\$ 200	\$ 800
3	1	LS	Mobilization	\$ 306345 ³²	\$ 306345 ³²
4	1	DOLLAR	Construction Layout	\$ 25000	\$ 25000
5	880	LF	Silt Fence	\$ 4	\$ 3520
6	7	UNIT	Haybale	\$ 0 ⁰¹	\$ 0 ⁰¹
7	7	UNIT	Inlet Filter, Type 2, 2' x 4'	\$ 75	\$ 525
8	8	UNIT	Breakaway barricade	\$ 120	\$ 960
9	50	UNIT	Drum	\$ 0 ⁰¹	\$ 0 ⁵⁰
10	50	UNIT	Traffic Cone	\$ 0 ⁰¹	\$ 0 ⁵⁰
11	849	SF	Construction Sign	\$ 15	\$ 12735
12	400	LF	Construction Barrier Curb	\$ 0 ⁰¹	\$ 4
13	4	UNIT	Flashing Arrow Board	\$ 0 ⁰¹	\$ 0 ⁰⁴
14	4	UNIT	Portable Variable Message Sign	\$ 2500	\$ 10000
15	4	UNIT	Traffic Control Truck with Mounted Crash Cushion	\$ 500	\$ 2000
16	1000	LF	Temporary Traffic Stripes, 4"	\$ 1	\$ 1000
17	100	SF	Temporary Traffic Markings	\$ 6	\$ 600
18	24	SF	Monmouth County Project Sign, 6' x 4'	\$ 35	\$ 840
19	1	ALL	Uniformed Police Officers Allowance	\$ 25,000.00	\$ 25,000.00
20	1	DOLLAR	Fuel price adjustment	\$ 15,000.00	\$ 15,000.00
21	1	DOLLAR	Asphalt price adjustment	\$ 15,000.00	\$ 15,000.00
22	1	LS	Vibration Monitoring	\$ 30000	\$ 30000
23	1	LS	Clearing Site	\$ 25000	\$ 25000
24	1	LS	Clearing Site, Bridge	\$ 75000	\$ 75000
25	1	LS	Temporary Shielding	\$ 0 ⁰¹	\$ 0 ⁰¹
26	20	CY	Excavation, test pits	\$ 125	\$ 2500
27	2178	CY	Excavation, Unclassified	\$ 0 ⁰¹	\$ 2178
28	2178	CY	Excavation, regulated material	\$ 0 ⁰¹	\$ 2178
29	3676	TON	Disposal of regulated material	\$ 10	\$ 36760
30	380	CY	I-9 Soil Aggregate	\$ 85	\$ 32300
31	120	CY	I-11 Soil aggregate	\$ 80	\$ 9600
32	2200	CY	I-14 Soil aggregate	\$ 55	\$ 121000
33	350	SY	Geotextile, roadway stabilization	\$ 5	\$ 1750
34	2850	SY	Dense graded aggregate base course, 6" thick	\$ 20	\$ 57000
35	3400	LF	Polymerized Joint Adhesive	\$ 2	\$ 6800

SCHEDULE OF QUANTITIES & PRICES

Project Entitled:
REPLACEMENT OF BRIDGE R-5
ON COUNTY ROUTE 39 (FLORENCE
AVENUE) OVER CHINGARORA CREEK
IN THE BOROUGH OF UNION BEACH,
MONMOUTH COUNTY, NEW JERSEY

MARBRO, INC.

F-53-2022

ITEM No.	EST. QTY.	UNIT	DESCRIPTION	UNIT PRICE	AMOUNT
36	415	TON	Hot Mix Asphalt 9.5M64 surface course	\$ 125	\$ 51875
37	1005	TON	Hot Mix Asphalt 19M64 base course	\$ 115	\$ 115575
38	1	LS	Temporary Cofferdam	\$ 95000	\$ 95000
39	1	LS	Permanent Cofferdam	\$ 95000	\$ 95000
40	1	LS	Furnishing Equipment for Driving Piles	\$ 825000	\$ 825000
41	240	LF	Test Pile, Furnished	\$ 62	\$ 14880
42	240	LF	Test Pile, Driven	\$ 5	\$ 1200
43	4	UNIT	Dynamic Pile Load Test	\$ 3600	\$ 14400
44	3400	LF	Cast-In-Place Concrete Pile, Furnished, 12.75" Diameter	\$ 62	\$ 210800
45	3400	LF	Cast-In-Place Concrete Pile, Driven, 12.75" Diameter	\$ 5	\$ 17000
46	72	UNIT	Pile Shoe	\$ 200	\$ 14400
47	28400	LB	Reinforcement Steel, Galvanized	\$ 2 ⁵⁰	\$ 71000
48	111	CY	Concrete Footing	\$ 550	\$ 61050
49	37	CY	Concrete Wing Wall	\$ 1800	\$ 66600
50	34	LF	Concrete Pylon, HPC	\$ 400	\$ 13600
51	45	LF	Precast Concrete Culvert (30'-0" Wide X 7'-10 7/8" High)	\$ 6500	\$ 292500
52	1	UNIT	Bridge Identification Plaque	\$ 2000	\$ 2000
53	32	CY	Concrete Bridge Deck, HPC	\$ 1400	\$ 44800
54	10	CY	Concrete Bridge Sidewalk, HPC	\$ 700	\$ 7000
55	82	LF	Steel 4-Bar Bridge Railing, Powder Coated Black	\$ 400	\$ 32800
56	60	LF	15" reinforced concrete pipe, class V	\$ 90	\$ 5400
57	113	LF	18" reinforced concrete pipe, class V	\$ 85	\$ 9605
58	270	LF	24" reinforced concrete pipe, class V	\$ 115	\$ 31050
59	128	LF	8" Perforated High Density Polyethylene Pipe	\$ 35	\$ 4480
60	1	UNIT	24" x 38" reinforced concrete end section	\$ 4000	\$ 4000
61	9	LF	24" x 38" reinforced concrete elliptical pipe, class HE-IV	\$ 500	\$ 4500
62	4	CY	Concrete headwall with apron	\$ 1500	\$ 6000
63	2	UNIT	Inlet, Type B, 6" Head	\$ 4000	\$ 8000
64	5	UNIT	Inlet, Type B, 8" Head	\$ 4000	\$ 20000
65	148	SY	Riprap stone slope protection, 14" thick (D50=7")	\$ 75	\$ 11100

SCHEDULE OF QUANTITIES & PRICES

Project Entitled:
**REPLACEMENT OF BRIDGE R-5
 ON COUNTY ROUTE 39 (FLORENCE
 AVENUE) OVER CHINGARORA CREEK
 IN THE BOROUGH OF UNION BEACH,
 MONMOUTH COUNTY, NEW JERSEY**
 F-53-2022

MARBRO, INC.

ITEM No.	EST. QTY.	UNIT	DESCRIPTION	UNIT PRICE	AMOUNT
66	56	SY	Riprap stone slope protection, 36" thick (D50=7")	\$ 100	\$ 5600
67	37	SY	Riprap stone channel protection, 14" thick (D50=7")	\$ 125	\$ 4625
68	5	SY	Riprap stone channel protection, 36" thick (D50=7")	\$ 100	\$ 500
69	605	LF	Temporary Chain-Link Fence, 8' High	\$ 8	\$ 4840
70	901	SY	Concrete sidewalk, 4" thick	\$ 95	\$ 85595
71	55	SY	Hot Mix Asphalt driveway, 6" thick, commercial	\$ 27	\$ 1485
72	42	SY	Concrete driveway, reinforced, 10" thick	\$ 160	\$ 6720
73	4	SY	Detectable warning surface	\$ 300	\$ 1200
74	1616	LF	6" x 8" x 20" concrete vertical curb	\$ 36	\$ 58176
75	135	SY	Non-vegetative surface, hot mix asphalt	\$ 66	\$ 8910
76	87.5	LF	Beam guide rail, powder coated black	\$ 60	\$ 5250
77	4	UNIT	Tangent guide rail terminal, powder coated black	\$ 5000	\$ 20000
78	4	UNIT	Approach guide rail transition TL-2, powder coated black	\$ 3500	\$ 14000
79	1548	LF	Traffic markings lines, 4" wide	\$ 150	\$ 2322
80	133	LF	Traffic markings lines, 24" wide	\$ 6	\$ 798
81	75	SF	Regulatory and warning sign	\$ 40	\$ 3000
82	3	UNIT	Reset water valve box	\$ 50	\$ 150
83	4	UNIT	Reconstruct manhole, sanitary sewer, using new casting	\$ 2000	\$ 8000
84	1254	LF	Video Inspection of 54" Dia. Gravity Sewer	\$ 8	\$ 10032
85	145	SY	Topsoiling, 5" thick	\$ 8	\$ 1160
86	20	CY	Borrow topsoil	\$ 75	\$ 1500
87	75	SY	Fertilizing and seeding, type W	\$ 5	\$ 375
88	70	SY	Fertilizing and seeding, type A-3	\$ 5	\$ 350
89	198	SY	Topsoil stabilization, type 1 mat	\$ 10	\$ 1980
90	70	SY	Straw Mulching	\$ 5	\$ 350

SCHEDULE OF QUANTITIES & PRICES

Project Entitled:

**REPLACEMENT OF BRIDGE R-5
ON COUNTY ROUTE 39 (FLORENCE
AVENUE) OVER CHINGARORA CREEK
IN THE BOROUGH UNION BEACH
MONMOUTH COUNTY, NEW JERSEY**

F-53-2022

MARBRO, INC.

TOTAL LUMP SUM BID ALL ITEMS 3,217,117 (Numeric)

Three million two hundred sixteen thousand one hundred
seventeen (Written)

CONTRACTOR: MARBRO, INC.

BY: FRANK MARUCCI JR
PRESIDENT (Printed)

Frank Marucci Jr
FRANK MARUCCI JR
PRESIDENT (Signature)

TITLE: _____

DATE: 10/19/22