

SIGNATURE PAGE

To the Board of County Commissioners of the County of Monmouth:

**THE UNDERSIGNED HEREBY DECLARES THAT
I (WE) HAVE CAREFULLY EXAMINED THE SPECIFICATIONS.
I (WE) HEREBY CERTIFY PRICES QUOTED ARE IN ACCORDANCE
WITH YOUR REQUIREMENTS.**

Company Name: Midlantic Construction LLC
(PRINT)

Preparer's Name: Michael Murray
(PRINT)

Signature:  10/26/22
(DATE)

Address: 371 N Main St
Barnegat, NJ 08005

Telephone No.: 732-223-9393

Fax No.: 732-223-2460

E-Mail Address: mmurray@midlanticconstllc.com

Contact Person: Michael Murray

FEIN:
(Federal Employee ID)

SCHEDULE OF QUANTITIES & PRICES

Project Entitled:

**REPLACEMENT OF BRIDGE R-5
ON COUNTY ROUTE 39 (FLORENCE
AVENUE) OVER CHINGARORA CREEK
IN THE BOROUGH OF UNION BEACH,
MONMOUTH COUNTY, NEW JERSEY**

F-53-2022

ITEM No.	EST. QTY.	UNIT	DESCRIPTION	UNIT PRICE	AMOUNT
1	1	LS	Progress Schedule	\$ 1,000.00	\$ 1,000.00
2	4	UNIT	Progress Schedule Update	\$ 100.00	\$ 400.00
3	1	LS	Mobilization	\$ 420,000.00	\$ 420,000.00
4	1	DOLLAR	Construction Layout	\$ 50,000.00	\$ 50,000.00
5	880	LF	Silt Fence	\$ 20.00	\$ 17,600.00
6	7	UNIT	Haybale	\$ 85.00	\$ 595.00
7	7	UNIT	Inlet Filter, Type 2, 2' x 4'	\$ 550.00	\$ 3,850.00
8	8	UNIT	Breakaway barricade	\$ 100.00	\$ 800.00
9	50	UNIT	Drum	\$ 100.00	\$ 5,000.00
10	50	UNIT	Traffic Cone	\$ 50.00	\$ 2,500.00
11	849	SF	Construction Sign	\$ 20.00	\$ 16,980.00
12	400	LF	Construction Barrier Curb	\$ 10.00	\$ 4,000.00
13	4	UNIT	Flashing Arrow Board	\$ 100.00	\$ 400.00
14	4	UNIT	Portable Variable Message Sign	\$ 100.00	\$ 400.00
15	4	UNIT	Traffic Control Truck with Mounted Crash Cushion	\$ 100.00	\$ 400.00
16	1000	LF	Temporary Traffic Stripes, 4"	\$ 1.00	\$ 1,000.00
17	100	SF	Temporary Traffic Markings	\$ 7.00	\$ 700.00
18	24	SF	Monmouth County Project Sign, 6' x 4'	\$ 85.00	\$ 2,040.00
19	1	ALL	Uniformed Police Officers Allowance	\$ 25,000.00	\$ 25,000.00
20	1	DOLLAR	Fuel price adjustment	\$ 15,000.00	\$ 15,000.00
21	1	DOLLAR	Asphalt price adjustment	\$ 15,000.00	\$ 15,000.00
22	1	LS	Vibration Monitoring	\$ 25,000.00	\$ 25,000.00
23	1	LS	Clearing Site	\$ 28,000.00	\$ 28,000.00
24	1	LS	Clearing Site, Bridge	\$ 300,000.00	\$ 300,000.00
25	1	LS	Temporary Shielding	\$ 100.00	\$ 100.00
26	20	CY	Excavation, test pits	\$ 0.01	\$ 0.20
27	2178	CY	Excavation, Unclassified	\$ 0.01	\$ 21.78
28	2178	CY	Excavation, regulated material	\$ 0.01	\$ 21.78
29	3676	TON	Disposal of regulated material	\$ 0.01	\$ 36.76
30	380	CY	I-9 Soil Aggregate	\$ 100.00	\$ 38,000.00
31	120	CY	I-11 Soil aggregate	\$ 130.00	\$ 15,600.00
32	2200	CY	I-14 Soil aggregate	\$ 0.01	\$ 22.00
33	350	SY	Geotextile, roadway stabilization	\$ 42.00	\$ 14,700.00
34	2850	SY	Dense graded aggregate base course, 6" thick	\$ 20.00	\$ 57,000.00
35	3400	LF	Polymerized Joint Adhesive	\$ 2.00	\$ 6,800.00

SCHEDULE OF QUANTITIES & PRICES

Project Entitled:

**REPLACEMENT OF BRIDGE R-5
ON COUNTY ROUTE 39 (FLORENCE
AVENUE) OVER CHINGARORA CREEK
IN THE BOROUGH OF UNION BEACH,
MONMOUTH COUNTY, NEW JERSEY**

F-53-2022

ITEM No.	EST. QTY.	UNIT	DESCRIPTION	UNIT PRICE	AMOUNT
36	415	TON	Hot-Mix Asphalt 9.5M64 surface course	\$ 150.00	\$ 62,250.00
37	1005	TON	Hot Mix Asphalt 19M64 base course	\$ 130.00	\$ 130,650.00
38	1	LS	Temporary Cofferdam	\$ 129,000.00	\$ 129,000.00
39	1	LS	Permanent Cofferdam	\$ 129,000.00	\$ 129,000.00
40	1	LS	Furnishing Equipment for Driving Piles	\$ 1,260,000.00	\$ 1,260,000.00
41	240	LF	Test Pile, Furnished	\$ 190.00	\$ 45,600.00
42	240	LF	Test Pile, Driven	\$ 5.00	\$ 1,200.00
43	4	UNIT	Dynamic Pile Load Test	\$ 5,750.00	\$ 23,000.00
44	3400	LF	Cast-In-Place Concrete Pile, Furnished, 12.75" Diameter	\$ 60.00	\$ 204,000.00
45	3400	LF	Cast-In-Place Concrete Pile, Driven, 12.75" Diameter	\$ 5.00	\$ 17,000.00
46	72	UNIT	Pile Shoe	\$ 155.00	\$ 11,160.00
47	28400	LB	Reinforcement Steel, Galvanized	\$ 3.00	\$ 85,200.00
48	111	CY	Concrete Footing	\$ 1,000.00	\$ 111,000.00
49	37	CY	Concrete Wing Wall	\$ 2,800.00	\$ 103,600.00
50	34	LF	Concrete Pylon, HPC	\$ 975.00	\$ 33,150.00
51	45	LF	Precast Concrete Culvert (30'-0" Wide X 7'-10 7/8" High)	\$ 6,000.00	\$ 270,000.00
52	1	UNIT	Bridge Identification Plaque	\$ 4,370.00	\$ 4,370.00
53	32	CY	Concrete Bridge Deck, HPC	\$ 1,525.00	\$ 48,800.00
54	10	CY	Concrete Bridge Sidewalk, HPC	\$ 3,000.00	\$ 30,000.00
55	82	LF	Steel 4-Bar Bridge Railing, Powder Coated Black	\$ 375.00	\$ 30,750.00
56	60	LF	15" reinforced concrete pipe, class V	\$ 185.00	\$ 11,100.00
57	113	LF	18" reinforced concrete pipe, class V	\$ 165.00	\$ 18,645.00
58	270	LF	24" reinforced concrete pipe, class V	\$ 140.00	\$ 37,800.00
59	128	LF	8" Perforated High Density Polyethylene Pipe	\$ 40.00	\$ 5,120.00
60	1	UNIT	24" x 38" reinforced concrete end section	\$ 4,600.00	\$ 4,600.00
61	9	LF	24" x 38" reinforced concrete elliptical pipe, class HE-IV	\$ 725.00	\$ 6,525.00
62	4	CY	Concrete headwall with apron	\$ 1,900.00	\$ 7,600.00
63	2	UNIT	Inlet, Type B, 6" Head	\$ 4,700.00	\$ 9,400.00
64	5	UNIT	Inlet, Type B, 8" Head	\$ 4,300.00	\$ 21,500.00
65	148	SY	Riprap stone slope protection, 14" thick (D50=7")	\$ 145.00	\$ 21,460.00

SCHEDULE OF QUANTITIES & PRICES

Project Entitled:

**REPLACEMENT OF BRIDGE R-5
ON COUNTY ROUTE 39 (FLORENCE
AVENUE) OVER CHINGARORA CREEK
IN THE BOROUGH OF UNION BEACH,
MONMOUTH COUNTY, NEW JERSEY**

F-53-2022

ITEM No.	EST. QTY.	UNIT	DESCRIPTION	UNIT PRICE	AMOUNT
66	56	SY	Riprap stone slope protection, 36" thick (D50=7")	\$ 360.00	\$ 20,160.00
67	37	SY	Riprap stone channel protection, 14" thick (D50=7")	\$ 175.00	\$ 6,475.00
68	5	SY	Riprap stone channel protection, 36" thick (D50=7")	\$ 1,080.00	\$ 5,400.00
69	605	LF	Temporary Chain-Link Fence, 8' High	\$ 2.00	\$ 1,210.00
70	901	SY	Concrete sidewalk, 4" thick	\$ 140.00	\$ 126,140.00
71	55	SY	Hot Mix Asphalt driveway, 6" thick, commercial	\$ 100.00	\$ 5,500.00
72	42	SY	Concrete driveway, reinforced, 10" thick	\$ 500.00	\$ 21,000.00
73	4	SY	Detectable warning surface	\$ 500.00	\$ 2,000.00
74	1616	LF	6" x 8" x 20" concrete vertical curb	\$ 35.00	\$ 56,560.00
75	135	SY	Non-vegetative surface, hot mix asphalt	\$ 55.00	\$ 7,425.00
76	87.5	LF	Beam guide rail, powder coated black	\$ 55.00	\$ 4,812.50
77	4	UNIT	Tangent guide rail terminal, powder coated black	\$ 4,000.00	\$ 16,000.00
78	4	UNIT	Approach guide rail transition TL-2, powder coated black	\$ 3,000.00	\$ 12,000.00
79	1548	LF	Traffic markings lines, 4" wide	\$ 2.00	\$ 3,096.00
80	133	LF	Traffic markings lines, 24" wide	\$ 7.00	\$ 931.00
81	75	SF	Regulatory and warning sign	\$ 80.00	\$ 6,000.00
82	3	UNIT	Reset water valve box	\$ 650.00	\$ 1,950.00
83	4	UNIT	Reconstruct manhole, sanitary sewer, using new casting	\$ 3,800.00	\$ 15,200.00
84	1254	LF	Video Inspection of 54" Dia. Gravity Sewer	\$ 7.00	\$ 8,778.00
85	145	SY	Topsoiling, 5" thick	\$ 58.00	\$ 8,410.00
86	20	CY	Borrow topsoil	\$ 100.00	\$ 2,000.00
87	75	SY	Fertilizing and seeding, type W	\$ 2.00	\$ 150.00
88	70	SY	Fertilizing and seeding, type A-3	\$ 2.00	\$ 140.00
89	198	SY	Topsoil stabilization, type 1 mat	\$ 20.00	\$ 3,960.00
90	70	SY	Straw Mulching	\$ 2.00	\$ 140.00

SCHEDULE OF QUANTITIES & PRICES

Project Entitled:

**REPLACEMENT OF BRIDGE R-5
ON COUNTY ROUTE 39 (FLORENCE
AVENUE) OVER CHINGARORA CREEK
IN THE BOROUGH UNION BEACH
MONMOUTH COUNTY, NEW JERSEY**


F-53-2022

TOTAL LUMP SUM BID ALL ITEMS 4,276,885.⁰² (Numeric)

Four Million Two Hundred Seventy Six Thousand Eight Hundred
Eighty Five Dollars and Two cents. (Written)

CONTRACTOR: Midlantic Construction LLC

BY: Michael Murray

 (Printed)
(Signature)

TITLE: President

DATE: 10/26/22