

SCHEDULE OF QUANTITIES & PRICES

Project Entitled:

**PHASE I PARKING LOT RESURFACING, SIDEWALK, AND ADA
IMPROVEMENTS AT THE MONMOUTH COUNTY COURTHOUSE
IN THE BOROUGH OF FREEHOLD, MONMOUTH COUNTY, NEW JERSEY
F #76-2021**

<u>ITEM NO.</u>	<u>ESTIMATED QUANTITY</u>		<u>ITEM</u>	<u>UNIT PRICE</u>	<u>AMOUNT</u>
1.	1,163	LF	SILT FENCE	\$ <u>3.00</u>	\$ <u>3,489.00</u>
2.	12	U	INLET FILTER TYPE 2, 2' X 4'	\$ <u>125.00</u>	\$ <u>1,500.00</u>
3.	2	U	INLET FILTER TYPE 2, 4' X 4'	\$ <u>250.00</u>	\$ <u>500.00</u>
4.	600	SF	SEDIMENT CONTROL BAG	\$ <u>50.00</u>	\$ <u>30,000.00</u>
5.	1	LS	CONCRETE WASHOUT SYSTEM	\$ <u>5,000.00</u>	\$ <u>5,000.00</u>
6.	1	U	OIL-ONLY EMERGENCY SPILL KIT, TYPE 1	\$ <u>5,000.00</u>	\$ <u>5,000.00</u>
7.	10	CY	EROSION CONTROL SEDIMENT REMOVAL	\$ <u>100.00</u>	\$ <u>1,000.00</u>
8.	2	U	PROJECT IDENTIFICATION SIGN, 4' X 6'	\$ <u>500.00</u>	\$ <u>1,000.00</u>
9.	1	LS	MAINTENANCE AND PROTECTION OF TRAFFIC	\$ <u>25,000.00</u>	\$ <u>25,000.00</u>
10.	12,000	DOLL	UNIFORMED POLICE OFFICERS ALLOWANCE	\$ <u>1</u>	\$ <u>12,000</u>
11.	400	DOLL	FUEL PRICE ADJUSTMENT	\$ <u>1</u>	\$ <u>400</u>
12.	600	DOLL	ASPHALT PRICE ADJUSTMENT	\$ <u>1</u>	\$ <u>600</u>
13.	1	LS	CLEARING SITE	\$ <u>35,000.00</u>	\$ <u>35,000.00</u>
14.	5	U	EXCAVATION, TEST PIT (IF AND WHERE DIRECTED)	\$ <u>500.00</u>	\$ <u>2,500.00</u>
15.	677	CY	EXCAVATION, UNCLASSIFIED	\$ <u>50.00</u>	\$ <u>33,850.00</u>
16.	802	SY	DENSE-GRADED AGGREGATE BASE COURSE, 6" THICK	\$ <u>12.00</u>	\$ <u>9,624.00</u>

SCHEDULE OF QUANTITIES & PRICES

Project Entitled:

**PHASE I PARKING LOT RESURFACING, SIDEWALK, AND ADA
IMPROVEMENTS AT THE MONMOUTH COUNTY COURTHOUSE
IN THE BOROUGH OF FREEHOLD, MONMOUTH COUNTY, NEW JERSEY
F #76-2021**

<u>ITEM NO.</u>	<u>ESTIMATED QUANTITY</u>		<u>ITEM</u>	<u>UNIT PRICE</u>	<u>AMOUNT</u>
17.	20,951	SY	HMA MILLING, 3" OR LESS	\$ <u>4.00</u>	\$ <u>83,804.00</u>
18.	3,068	LF	POLYMERIZED JOINT ADHESIVE	\$ <u>2.50</u>	\$ <u>7,670.00</u>
19.	1,741	GAL	TACK COAT	\$ <u>5.00</u>	\$ <u>8,705.00</u>
20.	2,615	T	HOT MIX ASPHALT 9.5 M 64 SURFACE COURSE	\$ <u>95.00</u>	\$ <u>248,425.00</u>
21.	294	T	HOT MIX ASPHALT 19 M 64 BASE COURSE	\$ <u>93.00</u>	\$ <u>27,342.00</u>
22.	12	LF	18" REINFORCED CONCRETE PIPE	\$ <u>200.00</u>	\$ <u>2,400.00</u>
23.	1	U	INLET, TYPE B	\$ <u>4,000.00</u>	\$ <u>4,000.00</u>
24.	1	U	INLET CONVERTED TO MANHOLE	\$ <u>3,750.00</u>	\$ <u>3,750.00</u>
25.	1	U	SET INLET TYPE A, CASTING	\$ <u>750.00</u>	\$ <u>750.00</u>
26.	8	U	SET INLET TYPE B, CASTING	\$ <u>750.00</u>	\$ <u>6,000.00</u>
27.	1	U	SET MANHOLE CASTING	\$ <u>500.00</u>	\$ <u>500.00</u>
28.	2	U	CLEANING DRAINAGE STRUCTURE (IF AND WHERE DIRECTED)	\$ <u>500.00</u>	\$ <u>1,000.00</u>
29.	654	SY	CONCRETE SIDEWALK, 4" THICK	\$ <u>90.00</u>	\$ <u>58,860.00</u>
30.	10	SY	CONCRETE ISLAND, 4" THICK	\$ <u>100.00</u>	\$ <u>1,000.00</u>
31.	23	SY	DETECTABLE WARNING SURFACE	\$ <u>300.00</u>	\$ <u>6,900.00</u>
32.	2,829	LF	6" X 8" X 20" CONCRETE VERTICAL CURB	\$ <u>38.75</u>	\$ <u>109,623.75</u>

SCHEDULE OF QUANTITIES & PRICES

Project Entitled:

**PHASE I PARKING LOT RESURFACING, SIDEWALK, AND ADA
IMPROVEMENTS AT THE MONMOUTH COUNTY COURTHOUSE
IN THE BOROUGH OF FREEHOLD, MONMOUTH COUNTY, NEW JERSEY
F #76-2021**

<u>ITEM NO.</u>	<u>ESTIMATED QUANTITY</u>		<u>ITEM</u>	<u>UNIT PRICE</u>	<u>AMOUNT</u>
33.	22,917	LF	TRAFFIC STRIPES, LONG-LIFE, THERMOPLASTIC, 4"	\$ <u>1.50</u>	\$ <u>34,375.50</u>
34.	221	SF	TRAFFIC MARKINGS SYMBOLS	\$ <u>10.00</u>	\$ <u>2,210.00</u>
35.	37	SF	REGULATORY AND WARNING SIGN	\$ <u>12.00</u>	\$ <u>444.00</u>
36.	28	U	RELOCATE SIGN	\$ <u>375.00</u>	\$ <u>10,500.00</u>
37.	1,787	SY	TOPSOIL SPREADING, 5" THICK	\$ <u>6.00</u>	\$ <u>10,722.00</u>
38.	1,787	SY	FERTILIZING AND SEEDING, TYPE 13	\$ <u>4.00</u>	\$ <u>7,148.00</u>
39.	1,787	SY	STRAW MULCHING	\$ <u>2.00</u>	\$ <u>3,574.00</u>


TOTAL LUMP SUM BID ALL ITEMS \$806,166.25

(Numeric)

Eight hundred six thousand one hundred sixty six dollars and twenty five cents
(Written)

CONTRACTOR: L&L Paving Company, Inc

BY: Lance Redaelli
(Printed)


(Signature)

TITLE: Vice President

DATE: 05/19/2021