

PROPOSAL
to the

**BOARD OF COUNTY COMMISSIONERS
COUNTY OF MONMOUTH, NEW JERSEY**

for the
Project Entitled:

**REPLACEMENT OF BRIDGE S-14
ON COUNTY ROUTE 50 (SWIMMING RIVER ROAD) OVER THE SWIMMING RIVER
IN THE TOWNSHIPS OF COLTS NECK AND MIDDLETOWN AND
BOROUGH OF TINTON FALLS, MONMOUTH COUNTY, NEW JERSEY**

F-83-2024

The undersigned hereby declare that he/she has carefully examined the Advertisement, Standard Specifications, Addendum(s) to Standard Specifications, Instructions to Bidders, Form of Contract and Bond for the Project named above; that he/she has carefully examined the site of the Project as provided in Section 102 of the 2019 Standard Specifications and that he/she will contract to carry out and complete said Project as specified and delineated at the prices per unit measure for each scheduled item of work stated in the Schedule of Prices.

It is understood that the total price, stated by the undersigned in the Schedule of Prices for the various item, is based on the estimated quantities and will control in the awarding of the Contract.

It is further understood that the quantities stated in this Schedule of Prices are estimates only and may be increased or decreased as provided for in the Specifications.


Submitted By:

The undersigned is a Partnership, an individual, or a Corporation under the laws of the State of New Jersey, having principal offices at

CONTRACTOR: Midlantic Construction LLC

ADDRESS: 371 N. Main St., Barnegat, NJ 08005

TELEPHONE: 732-223-9393 **FAX:** 732-223-2461

BY: Michael Murray

(Printed)
(Signed)

TITLE: President

DATE: 02/12/2025

SCHEDULE OF QUANTITIES & PRICES

Project Entitled:

**REPLACEMENT OF BRIDGE S-14
ON COUNTY ROUTE 50 (SWIMMING RIVER ROAD) OVER THE SWIMMING RIVER
IN THE TOWNSHIPS OF COLTS NECK AND MIDDLETOWN AND
BOROUGH OF TINTON FALLS, MONMOUTH COUNTY, NEW JERSEY**

F-83-2024

<u>ITEM NO.</u>	<u>ESTIMATED QUANTITY</u>	<u>ITEM</u>	<u>UNIT PRICE</u>	<u>AMOUNT</u>
1.	1 LS	PROGRESS SCHEDULE	\$ <u>1,000.00</u>	\$ <u>1,000.00</u>
2.	1 LS	MOBILIZATION	\$ <u>1,050,000.00</u>	\$ <u>1,050,000.00</u>
3.	1 U	FIELD OFFICE TYPE B SET UP	\$ <u>24,500.00</u>	\$ <u>24,500.00</u>
4.	21 MO	FIELD OFFICE TYPE B MAINTENANCE	\$ <u>3,100.00</u>	\$ <u>65,100.00</u>
5.	1 U	MONUMENT	\$ <u>230.00</u>	\$ <u>230.00</u>
6.	1,041 LF	SILT FENCE	\$ <u>15.00</u>	\$ <u>15,615.00</u>
7.	52 U	HAYBALE	\$ <u>1.00</u>	\$ <u>52.00</u>
8.	9 U	INLET FILTER TYPE 2, 2' X 4'	\$ <u>10.00</u>	\$ <u>90.00</u>
9.	341 LF	FLOATING TURBIDITY BARRIER, TYPE 2	\$ <u>30.00</u>	\$ <u>10,230.00</u>
10.	2 U	SEDIMENT CONTROL BAG	\$ <u>130.00</u>	\$ <u>260.00</u>
11.	1 LS	CONCRETE WASHOUT SYSTEM	\$ <u>2,900.00</u>	\$ <u>2,900.00</u>
12.	2 U	OIL ONLY EMERGENCY SPILL KIT, TYPE 1	\$ <u>1,600.00</u>	\$ <u>3,200.00</u>
13.	20 CY	EROSION CONTROL SEDIMENT REMOVAL	\$ <u>0.01</u>	\$ <u>0.20</u>

SCHEDULE OF QUANTITIES & PRICES

Project Entitled:

**REPLACEMENT OF BRIDGE S-14
ON COUNTY ROUTE 50 (SWIMMING RIVER ROAD) OVER THE SWIMMING RIVER
IN THE TOWNSHIPS OF COLTS NECK AND MIDDLETOWN AND
BOROUGH OF TINTON FALLS, MONMOUTH COUNTY, NEW JERSEY**

F-83-2024

<u>ITEM NO.</u>	<u>ESTIMATED QUANTITY</u>		<u>ITEM</u>	<u>UNIT PRICE</u>	<u>AMOUNT</u>
14.	11 U		BREAKAWAY BARRICADE	\$ <u>10.00</u>	\$ <u>110.00</u>
15.	42 U		DRUM	\$ <u>10.00</u>	\$ <u>420.00</u>
16.	400 SF		CONSTRUCTION SIGNS	\$ <u>1.00</u>	\$ <u>400.00</u>
17.	2 U		PROJECT IDENTIFICATION SIGN, 4' X 6'	\$ <u>1,000.00</u>	\$ <u>2,000.00</u>
18.	1,280 LF		CONSTRUCTION BARRIER CURB	\$ <u>0.01</u>	\$ <u>12.80</u>
19.	1 U		ARROW BOARD, 4' X 8'	\$ <u>0.01</u>	\$ <u>0.01</u>
20.	1 U		TRAFFIC CONTROL TRUCK WITH MOUNTED CRASH CUSHION	\$ <u>30,000.00</u>	\$ <u>30,000.00</u>
21.	13,120 LF		TEMPORARY TRAFFIC STRIPES, 4"	\$ <u>0.50</u>	\$ <u>6,560.00</u>
22.	4 U		TEMPORARY CRASH CUSHION, COMPRESSIVE BARRIER, TYPE 3, WIDTH NARROW	\$ <u>0.01</u>	\$ <u>0.04</u>
23.	45,000 DOLL		UNIFORMED POLICE OFFICERS ALLOWANCE	\$ <u>1.00</u>	\$ <u>45,000.00</u>
24.	4,000 DOLL		FUEL PRICE ADJUSTMENT	\$ <u>1.00</u>	\$ <u>4,000.00</u>
25.	4,300 DOLL		ASPHALT PRICE ADJUSTMENT	\$ <u>1.00</u>	\$ <u>4,300.00</u>
26.	38,340 DOLL		STEEL PRICE ADJUSTMENT	\$ <u>1.00</u>	\$ <u>38,340.00</u>
27.	1 LS		VIBRATION MONITORING	\$ <u>15,000.00</u>	\$ <u>15,000.00</u>

SCHEDULE OF QUANTITIES & PRICES

Project Entitled:

**REPLACEMENT OF BRIDGE S-14
 ON COUNTY ROUTE 50 (SWIMMING RIVER ROAD) OVER THE SWIMMING RIVER
 IN THE TOWNSHIPS OF COLTS NECK AND MIDDLETOWN AND
 BOROUGH OF TINTON FALLS, MONMOUTH COUNTY, NEW JERSEY**

F-83-2024

<u>ITEM NO.</u>	<u>ESTIMATED QUANTITY</u>	<u>ITEM</u>	<u>UNIT PRICE</u>	<u>AMOUNT</u>
28.	1 LS	CLEARING SITE	\$ 50,000.00	\$ 50,000.00
29.	1 LS	CLEARING SITE, BRIDGE S-14	\$ 150,000.00	\$ 150,000.00
30.	1 LS	TEMPORARY SHIELDING	\$ 5,000.00	\$ 5,000.00
31.	10 CY	EXCAVATION, TEST PIT	\$ 0.01	\$ 0.10
32.	6,438 CY	EXCAVATION, UNCLASSIFIED	\$ 96.00	\$ 618,048.00
33.	1,802 SY	REMOVAL OF PAVEMENT	\$ 7.00	\$ 12,614.00
34.	1,663 T	DISPOSAL OF REGULATED MATERIAL	\$ 0.01	\$ 16.63
35.	2 U	SOIL SAMPLING AND ANALYSES, REGULATED	\$ 2,300.00	\$ 4,600.00
36.	832 T	DISPOSAL OF ACID PRODUCING SOIL	\$ 0.01	\$ 8.32
37.	1,705 CY	I-5 SOIL AGGREGATE	\$ 70.00	\$ 119,350.00
38.	681 CY	I-9 SOIL AGGREGATE	\$ 114.00	\$ 77,634.00
39.	50 CY	I-14 SOIL AGGREGATE	\$ 50.00	\$ 2,500.00
40.	3,343 SY	DENSE-GRADED AGGREGATE BASE COURSE, 6" THICK	\$ 19.00	\$ 63,517.00
41.	168 CY	COARSE AGGREGATE, SIZE NO. 57	\$ 108.00	\$ 18,144.00

SCHEDULE OF QUANTITIES & PRICES

Project Entitled:

**REPLACEMENT OF BRIDGE S-14
ON COUNTY ROUTE 50 (SWIMMING RIVER ROAD) OVER THE SWIMMING RIVER
IN THE TOWNSHIPS OF COLTS NECK AND MIDDLETOWN AND
BOROUGH OF TINTON FALLS, MONMOUTH COUNTY, NEW JERSEY**

F-83-2024

<u>ITEM NO.</u>	<u>ESTIMATED QUANTITY</u>		<u>ITEM</u>	<u>UNIT PRICE</u>	<u>AMOUNT</u>
42.	1,381 SY		RUBBLIZE ASPHALT PAVEMENT	\$ 12.00	\$ 16,572.00
43.	2,108 SY		HMA MILLING, 3" OR LESS	\$ 6.00	\$ 12,648.00
44.	250 SY		HMA MILLING, MORE THAN 3" TO 6"	\$ 10.00	\$ 2,500.00
45.	5,701 LF		POLYMERIZED JOINT ADHESIVE	\$ 1.00	\$ 5,701.00
46.	371 GAL		TACK COAT	\$ 10.00	\$ 3,710.00
47.	570 T		HOT MIX ASPHALT 9.5 M 64 SURFACE COURSE	\$ 148.00	\$ 84,360.00
48.	1,635 T		HOT MIX ASPHALT 19 M 64 BASE COURSE	\$ 138.00	\$ 225,630.00
49.	2,700 SF		PERMANENT SHEETING	\$ 375.00	\$ 1,012,500.00
50.	1 LS		PERMANENT COFFERDAM	\$ 1,750,000.00	\$ 1,750,000.00
51.	1 LS		FURNISHING EQUIPMENT FOR DRIVING PILES	\$ 1,675,000.00	\$ 1,675,000.00
52.	540 LF		TEST PILE, FURNISHED	\$ 150.00	\$ 81,000.00
53.	540 LF		TEST PILE, DRIVEN	\$ 25.00	\$ 13,500.00
54.	6 U		DYNAMIC PILE LOAD TEST	\$ 5,500.00	\$ 33,000.00
55.	10,442 LF		CAST-IN-PLACE CONCRETE PILE, FURNISHED, 14" DIAMETER	\$ 78.00	\$ 814,476.00

SCHEDULE OF QUANTITIES & PRICES

Project Entitled:

**REPLACEMENT OF BRIDGE S-14
ON COUNTY ROUTE 50 (SWIMMING RIVER ROAD) OVER THE SWIMMING RIVER
IN THE TOWNSHIPS OF COLTS NECK AND MIDDLETOWN AND
BOROUGH OF TINTON FALLS, MONMOUTH COUNTY, NEW JERSEY**

F-83-2024

<u>ITEM NO.</u>	<u>ESTIMATED QUANTITY</u>		<u>ITEM</u>	<u>UNIT PRICE</u>	<u>AMOUNT</u>
56.	10,442 LF		CAST-IN-PLACE CONCRETE PILE, DRIVEN, 14" DIAMETER	\$ 7.50	\$ 78,315.00
57.	6 U		RESTRIKE WITH PDA AND CAPWAP ANALYSIS	\$ 1,700.00	\$ 10,200.00
58.	169,486 LB		REINFORCEMENT STEEL, GALVANIZED	\$ 2.25	\$ 381,343.50
59.	337 CY		CONCRETE FOOTING	\$ 675.00	\$ 227,475.00
60.	114 CY		CONCRETE WINGWALL	\$ 1,200.00	\$ 136,800.00
61.	267 CY		CONCRETE ABUTMENT WALL	\$ 855.00	\$ 228,285.00
62.	177 CY		CONCRETE PIER COLUMN AND CAP	\$ 715.00	\$ 126,555.00
63.	71 SY		EPOXY WATERPROOFING	\$ 68.00	\$ 4,828.00
64.	1,235 LF		PRESTRESSED CONCRETE BEAM (PENNDOT BEAM 20X36)	\$ 432.00	\$ 533,520.00
65.	36 U		REINFORCED ELASTOMERIC BEARING ASSEMBLY	\$ 1,550.00	\$ 55,800.00
66.	258 CY		CONCRETE BRIDGE DECK	\$ 1,635.00	\$ 421,830.00
67.	59 CY		CONCRETE BRIDGE SIDEWALK	\$ 850.00	\$ 50,150.00
68.	367 LF		CONCRETE BRIDGE PARAPET	\$ 318.00	\$ 116,706.00
69.	141 CY		CONCRETE BRIDGE APPROACH	\$ 1,065.00	\$ 150,165.00

SCHEDULE OF QUANTITIES & PRICES

Project Entitled:

**REPLACEMENT OF BRIDGE S-14
ON COUNTY ROUTE 50 (SWIMMING RIVER ROAD) OVER THE SWIMMING RIVER
IN THE TOWNSHIPS OF COLTS NECK AND MIDDLETOWN AND
BOROUGH OF TINTON FALLS, MONMOUTH COUNTY, NEW JERSEY**

F-83-2024

<u>ITEM NO.</u>	<u>ESTIMATED QUANTITY</u>		<u>ITEM</u>	<u>UNIT PRICE</u>	<u>AMOUNT</u>
70.	6,246 SF		TEMPORARY SHEETING	\$ 0.01	\$ 62.46
71.	1 U		IDENTIFICATION PLAQUE, 22"X22"	\$ 2,050.00	\$ 2,050.00
72.	24 U		UTILITY SUPPORT, BRIDGE	\$ 1,500.00	\$ 36,000.00
73.	20 LF		15" REINFORCED CONCRETE PIPE	\$ 238.00	\$ 4,760.00
74.	491 LF		18" REINFORCED CONCRETE PIPE	\$ 107.00	\$ 52,537.00
75.	104 LF		24" REINFORCED CONCRETE PIPE	\$ 120.00	\$ 12,480.00
76.	1 U		INLET, TYPE A	\$ 5,100.00	\$ 5,100.00
77.	4 U		INLET, TYPE B	\$ 5,450.00	\$ 21,800.00
78.	2 U		INLET, TYPE DOUBLE B	\$ 6,500.00	\$ 13,000.00
79.	3 U		SET INLET TYPE E, CASTING	\$ 2,750.00	\$ 8,250.00
80.	1 U		RECONSTRUCTED INLET, TYPE B, USING NEW CASTING	\$ 2,850.00	\$ 2,850.00
81.	1 U		RECONSTRUCTED MANHOLE, USING NEW CASTING	\$ 3,025.00	\$ 3,025.00
82.	283 SY		RIPRAP STONE CHANNEL PROTECTION, 18" THICK (D50=9")	\$ 0.01	\$ 2.83
83.	143 SY		RIPRAP STONE CHANNEL PROTECTION, 27" THICK (D50=9")	\$ 0.01	\$ 1.43

SCHEDULE OF QUANTITIES & PRICES

Project Entitled:

**REPLACEMENT OF BRIDGE S-14
 ON COUNTY ROUTE 50 (SWIMMING RIVER ROAD) OVER THE SWIMMING RIVER
 IN THE TOWNSHIPS OF COLTS NECK AND MIDDLETOWN AND
 BOROUGH OF TINTON FALLS, MONMOUTH COUNTY, NEW JERSEY**

F-83-2024

<u>ITEM NO.</u>	<u>ESTIMATED QUANTITY</u>	<u>ITEM</u>	<u>UNIT PRICE</u>	<u>AMOUNT</u>
84.	22 SY	GROUTED RIPRAP ARMORING, 18" THICK	\$ 0.01	\$ 0.22
85.	471 SY	RESET RIPRAP STONE SLOPE PROTECTION	\$ 1.00	\$ 471.00
86.	302 LF	CHAIN-LINK FENCE, 6' HIGH, POWDER COATED	\$ 108.00	\$ 32,616.00
87.	1 U	GATE, CHAIN-LINK FENCE, 6' WIDE, POWDER COATED	\$ 4,600.00	\$ 4,600.00
88.	741 SY	CONCRETE SIDEWALK, 4" THICK	\$ 150.00	\$ 111,150.00
89.	53 SY	HOT MIX ASPHALT DRIVEWAY, 6" THICK	\$ 86.00	\$ 4,558.00
90.	38 SY	CONCRETE DRIVEWAY, REINFORCED, 6" THICK	\$ 166.00	\$ 6,308.00
91.	6 SY	DETECTABLE WARNING SURFACE	\$ 660.00	\$ 3,960.00
92.	1,685 LF	6" X 8" X 20" CONCRETE VERTICAL CURB	\$ 50.00	\$ 84,250.00
93.	260 SY	NONVEGETATIVE SURFACE, HOT MIX ASPHALT	\$ 58.00	\$ 15,080.00
94.	252 LF	BEAM GUIDE RAIL, POWDER COATED	\$ 80.00	\$ 20,160.00
95.	3 U	TANGENT GUIDE RAIL TERMINAL, POWDER COATED	\$ 5,500.00	\$ 16,500.00
96.	4 U	APPROACH GUIDE RAIL TRANSITION TL-3, POWDER COATED	\$ 5,900.00	\$ 23,600.00
97.	4,640 LF	TRAFFIC STRIPES, LONG-LIFE, THERMOPLASTIC, 4"	\$ 1.00	\$ 4,640.00

SCHEDULE OF QUANTITIES & PRICES

Project Entitled:

**REPLACEMENT OF BRIDGE S-14
 ON COUNTY ROUTE 50 (SWIMMING RIVER ROAD) OVER THE SWIMMING RIVER
 IN THE TOWNSHIPS OF COLTS NECK AND MIDDLETOWN AND
 BOROUGH OF TINTON FALLS, MONMOUTH COUNTY, NEW JERSEY**

F-83-2024

<u>ITEM NO.</u>	<u>ESTIMATED QUANTITY</u>		<u>ITEM</u>	<u>UNIT PRICE</u>	<u>AMOUNT</u>
98.	22 U		RPM, BI-DIRECTIONAL, AMBER LENS	\$ 98.00	\$ 2,156.00
99.	4,210 LF		REMOVAL OF TRAFFIC STRIPES	\$ 2.00	\$ 8,420.00
100.	1 U		CRASH CUSHION, COMPRESSIVE BARRIER, TYPE 3, WIDTH NARROW, POWDER COATED	\$ 45,000.00	\$ 45,000.00
101.	26 SF		REGULATORY AND WARNING SIGN	\$ 58.00	\$ 1,508.00
102.	7 U		RESET WATER VALVE BOX	\$ 145.00	\$ 1,015.00
103.	2 U		RESET MANHOLE, SANITARY SEWER, USING NEW CASTING	\$ 1,100.00	\$ 2,200.00
104.	2 U		RESET GAS VALVE BOX	\$ 145.00	\$ 290.00
105.	9,000 DOLL		RESTORE STREET LIGHTING	\$ 1.00	\$ 9,000.00
106.	1 LS		TEMPORARY HIGHWAY LIGHTING SYSTEM	\$ 1,000.00	\$ 1,000.00
107.	1,242 SY		TOPSOIL SPREADING, 5" THICK	\$ 30.00	\$ 37,260.00
108.	1,242 SY		FERTILIZING AND SEEDING, TYPE 13	\$ 1.00	\$ 1,242.00
109.	277 SY		GREEN TOPSOIL STABILIZATION MATTING	\$ 4.00	\$ 1,108.00
110.	1,242 SY		STRAW MULCHING	\$ 1.00	\$ 1,242.00
111.	5,100 SF		STONE VENEER	\$ 82.00	\$ 418,200.00

SCHEDULE OF QUANTITIES & PRICES

Project Entitled:

**REPLACEMENT OF BRIDGE S-14
ON COUNTY ROUTE 50 (SWIMMING RIVER ROAD) OVER THE SWIMMING RIVER
IN THE TOWNSHIPS OF COLTS NECK AND MIDDLETOWN AND
BOROUGH OF TINTON FALLS, MONMOUTH COUNTY, NEW JERSEY**

F-83-2024

<u>ITEM NO.</u>	<u>ESTIMATED QUANTITY</u>	<u>ITEM</u>	<u>UNIT PRICE</u>	<u>AMOUNT</u>
112.	5,100 SF	CLEAR SEALER FOR STONE VENEER	\$ <u>1.00</u>	\$ <u>5,100.00</u>
113.	2 U	PORTABLE VARIABLE MESSAGE SIGN	\$ <u>2,000.00</u>	\$ <u>4,000.00</u>


TOTAL LUMP SUM BID ALL ITEMS \$ 11,721,874.54

(Numeric)
eleven million seven hundred twenty one thousand eight hundred
seventy four dollars and fifty four cents
(Written)

CONTRACTOR: Midlantic Construction LLC

BY: Michael Murray

(Printed)


(Signature)

TITLE: President

DATE: 02/12/2025