

SIGNATURE PAGE


P-46-2024

To the Monmouth County Board of County Commissioners:

**THE UNDERSIGNED HEREBY DECLARES THAT
I (WE) HAVE CAREFULLY EXAMINED THE SPECIFICATIONS.
I (WE) HEREBY CERTIFY PRICES QUOTED ARE IN ACCORDANCE
WITH YOUR REQUIREMENTS.**

Company Name: NV5 Northeast, Inc.
(PRINT)

Preparer's Name: Brian D. Arone
(PRINT)

Signature:  9/9/24
(DATE)

Address: 903 E. Hazelwood Ave
Rahway, NJ 07065

Telephone No.: 732-382-3553

Fax No.: 732-382-8840

E-Mail Address: brian.arone@nv5.com
*****(This should be the email where Contracts would be sent)*****

Contact Person: Brian D. Arone

FEIN: 

(Federal Employee ID)
BRC: 

(Business Registration
Certificate)

(Revised 2/2017)

FEE SCHEDULE FORM

ASCE GRADE	EQUIVALENT FEDERAL GENERAL SCHEDULE GRADE	EQUIVALENT FIRM TITLE (TO BE ADDED BY FIRM)	BILLING RATE
Clerical			
ETI			
ETII			
ETIII			
ETIV			
ETV			
PI	GS-5	Inspector	\$80.00/hr
PII	GS-7	Senior Inspector	\$91.00/hr
PIII	GS-9		
PIV	GS-11	Project Manager	\$116.00/hr
PV	GS-12	Senior Project Manger	\$156.00/hr
PVI	GS-13	Professional Engineer	\$177.00/hr
PVII	GS-14		
PVIII	GS-15		
PIX	Senior Executive Service	Vice President	\$215.00/hr

DIRECT EXPENSES	UNIT COST(S)
Reproduction	\$0.55/page
Postage/Delivery	at cost
Transportation Cost Per Mileage	\$0.64/mile

NOTE:

1. Billing Rate shall include all overhead, profit and employee benefits.

TOTAL PROJECT COST	\$100,000.00
---------------------------	---------------------

FEE SCHEDULE FORM

		<u>Billing Rate</u>
<u>CONCRETE</u>		
I. <u>Preliminary Test of Aggregates</u>		
<u>Fine Aggregate</u>		
(a)	Sieve Analysis & Fineness Modulus:	
	A.S.T.M. C-33 (C-136)..... per sample	<u>\$75.00</u>
(b)	Specific gravity & absorption: A.S.T.M. C-128... per sample	<u>\$65.00</u>
(c)	Organic impurities: A.S.T.M. C-40..... per sample	<u>\$40.00</u>
(d)	Silt & Clay: A.S.T.M. C-117..... per sample	<u>\$50.00</u>
(e)	Unit weight & void content: A.S.T.M. C-29..... per sample	<u>\$50.00</u>
(f)	Strength Comparison: A.S.T.M. C-87..... per sample	<u>\$140.00</u>
(g)	Efflorescence: A.S.T.M. C-67..... per sample	<u>\$105.00</u>
(h)	Soundness (Sodium or Magnesium Sulfate: A.S.T.M. C-88	
	First five (5) cycles.....	<u>\$185.00</u>
	Each additional cycle.....	<u>\$40.00</u>
<u>Coarse Aggregate</u>		
(a)	Sieve Analysis & Fineness Modulus:	
	A.S.T.M. C-33 (C-136)..... per sample	<u>\$75.00</u>
(b)	Specific gravity & absorption: A.S.T.M. C-127... per sample	<u>\$65.00</u>
(c)	Organic impurities: A.S.T.M. C-40..... per sample	<u>\$40.00</u>
(d)	Unit weight & void content: A.S.T.M. C-29..... per sample	<u>\$50.00</u>
(e)	Abrasion (Los Angeles): A.S.T.M. C-131..... per sample	<u>\$225.00</u>
(f)	Deleterious substances: A.S.T.M. C-33..... per sample	<u>\$50.00</u>
(g)	Soundness: (Sodium or Magnesium Sulfate): A.S.T.M. C-88	
	First Five (5) cycles.....	<u>\$180.00</u>
	Each additional cycle.....	<u>\$40.00</u>
(h)	Modified Proctor ----- \$300.00/sample	
(i)	Standard Proctor ----- \$275.00/sample	

FEE SCHEDULE FORM

Billing Rate

CONCRETE

II. Concrete Design Mix

- (a) Review mixes submitted for approval designed by others..... per mix \$85.00
- (b) Preliminary mix design recommendation A.C.I. 301.....per mix \$175.00
- (c) Fabricate, cap, cure, test & report 6" x 12" Test cylinders to confirm concrete design mix.....per cylinder \$38.00
- (d) Fabricate, cure, test & report flexure beam Test specimens to confirm concrete design mix.....per beam \$68.00

III. Controlled Concrete

- (a) Batch Plant Inspector
Furnish a technical inspector to be placed at the batch plant or the project site to assure that only the approved materials are used; observe mixing and placing of concrete, fabricate test cylinders, conduct slump test, air test, monitor temperature and check yield as required.....per day \$440.00
- (b) Field Inspector
Furnish a technical inspector to be placed at the project site to observe the mixing and placing of concrete, fabricate the required number of 6" x 12" test cylinders (or beams), conduct slump test, air test, monitor temperatures, and check yield as required.....per day \$440.00
- (c) Senior Field Inspector
As well as item (b), this inspector to check forms for cleanliness and mortar tightness. Also he shall review blueprints and check placements of reinforcing steel to assure proper placement (spacing, ties, laps), size and quantity of bars.....per day \$495.00

IV. Test Cylinders

- (a) Cap, cure, test and report results of 6" x 12" test cylinders.....per cylinder \$17.00
- (b) Transportation of test cylinders.....per trip \$65.00

FEE SCHEDULE FORM

Billing Rate

CONCRETE

V. Core Drilling

- (a) Supply one drilling unit and labor to obtain specimens of hardened concrete A.S.T.M. C-42 (4 ½ diameter or less) * minimum \$900.00/day
 - verticalper linear ft. *
 - horizontalper linear ft. *
- (b) Prepare concrete cores for compression testing.....per core \$45.00
- (c) Compression tests & reports.....per core \$18.00

VI. Chemical Analysis

- (a) Chemical analysis of hardened concrete A.S.T.M. C-85per sample \$810.00
- (b) Chloride content testing and analysis A.S.T.M. C-1218per sample \$210.00

VII. Winsor Probes Test of Hardened Concrete

- (a) Furnish a technical inspector along with Windsor Probe apparatus to test in-place concrete per day \$440.00
 plus per probe \$50.00

VIII. Swiss Hammer Test of Hardened Concrete

- (a) Furnish a technical inspector along with Swiss Hammer apparatus to test in-place concrete per day \$440.00

FEE SCHEDULE FORM

	<u>Billing Rate</u>
<u>BITUMINOUS CONCRETE</u>	
<u>I. Preliminary Test of Aggregates – N.J.D.O.T. Specifications</u>	
(a) Sieve analysis (dry)per sample	<u>\$65.00</u>
(b) Sieve analysis (wet)per sample	<u>\$70.00</u>
(c) Abrasion (Los Angeles) per sample	<u>\$335.00</u>
(d) Absorption & specific gravityper sample	<u>\$50.00</u>
(e) Clay & clay lumps.....per sample	<u>\$45.00</u>
(f) Organic impuritiesper sample	<u>\$35.00</u>
(g) Soundness (Sodium Sulfate) five (5) cycles....per sample	<u>\$300.00</u>
<u>II. Bituminous Mix Design – N.J.D.O.T. Specifications</u>	
(a) Marshall Methodper mix	<u>\$825.00</u>
<u>III. Quality Control Test – N.J.D.O.T. Specifications</u>	
(a) Extraction analysis per sample	<u>\$82.00</u>
(b) Stability & flowper sample	<u>\$52.00</u>
(c) Bulk Specific gravity (density determination),per sample	<u>\$57.00</u>
(d) Maximum theoretical specific gravity by A.S.T.M. D2041.....per sample	<u>\$82.00</u>
<u>IV. Plant Control & Inspection – N.J.D.O.T. Specification</u>	
(a) Furnish a technician to witness all weighting of delivery trucks and accordingly determine the quantity of materials furnished to the project.....per day	<u>\$495.00</u>
(b) Furnish an asphalt mixing plant inspector to witness the loading of all materials and to make continuous temperature checks of finished products; this inspector shall also take samples of materials and perform all quality control test as per the specifications.....per day	<u>\$505.00</u>

FEE SCHEDULE FORM

Billing Rate

BITUMINOUS CONCRETE

V. Field inspection

(a) Furnish an inspector at the field site to witness the preparing of sub-base and tack coat as well as witness placing all asphaltic materials to determine the thickness of material being laid and to see that it is properly compacted and rolled.....per day \$420.00

(b) Nuclear Density Testing

Furnish a certified senior inspector to monitor compaction on effort during lay down operation or to obtain data for acceptance criteria..... per day \$495.00

VI. Core Drilling

(a) Supply one drilling unit and labor to obtain specimens of finished pavement:

6" diameter per linear foot --

8" diameter per linear foot --

Minimum day \$900.00*

*This not not include traffic control

PIPE PRECAST, PILES

I. Manufacturing Inspection

(a) Place a technical inspector at point of fabrication to observe all phases of production and to witness and monitor all quality control test as required by the governing specification.

Precast Concrete Pipeper day \$495.00

Asbestos Cement Pipeper day \$495.00

Poly Vinyl Chloride Pipeper day \$495.00

Vitrified Clay Pipeper day \$495.00

Ductile Iron Pipeper day \$495.00

Steel Pipeper day \$495.00

Manholesper day \$495.00

Precast Pilesper day \$495.00

Precast Beam, Column & Architectural Memberper day \$495.00

FEE SCHEDULE FORM

Billing Rate

PIPE PRECAST, PILES (cont.)

II. Piles (wood, steel, concrete, Franki)

- (a) Pile Driving Inspection
Senior inspector to check driving rig, hammer,
pile dimensions, monitor blow count and determine
tip and cut off elevations.....per day \$600.00

- (b) Pile Driving Inspection
Professional Engineer to check driving rig, hammer,
pile dimension, monitor blow count and determine
top and cut-off elevationsper hour \$160.00

STRUCTURAL STEEL

I. Plant Inspection

- (a) Place a technical inspector at the point of fabrication to
monitor all dimensions, painting, bolt hole placement, shop welds
and any other required inspections.....per hour \$100.00

II. Field Inspection

- (a) Inspector to test high strength bolts for proper torque....per hour \$100.00

- (b) Inspector to check plumbness of erected membersper hour \$100.00

- (c) Inspector to visually inspect field welding at job site.....per hour \$100.00

